

Number	22-003184-PR01 (NW-B01-03-en-01)
Owner	AESTECH PORTUGAL, LDA Alameda dos Oceanos 142, Ground Floor– Door 0C, 1990-502 Lissabon Portugal
Product	SG façade
Designation	System: FG Aestech
Details	Manufacturer PEC Group GmbH; Material Glass with Fibre-reinforced plastic (FRP); Overall dimensions (W x H x D) 4164 mm x 6220 mm x 2230 mm;
Special features	Application in Europe is subject to approval of the construction as set out by the "Guideline for European Technical Approval for Structural Sealant Glazing Systems" ETAG No. 002

Results **)

Impact Resistance according to EN 14019:2016-06



Class: I5/E5

**) Decision rule: For the evaluation of conformity, the measurement uncertainty was not taken into account.

Basis *)

EN 13830:2003-09

*) and corresponding national versions
e.g. DIN EN)

Test report: 22-003184-PR01 PB-
B01-03-en-01

Representation



Instruction for use

The manufacturer is allowed to use the results obtained for preparing a Declaration of Performance in accordance with the Construction Products Regulation 305/2011/EC. Observe the specifications set out by the applicable product standard

Validity

The data and results refer solely to the tested and described specimen. Classification remains valid as long as the product and the above basis remain unchanged. The results can be extrapolated under the manufacturer's own liability subject to observance of the relevant specifications set out by the applicable product standard. This test/evaluation does not allow any statement to be made on any further characteristics regarding performance and quality of the construction presented, in particular the effects of weathering and ageing were not taken into account.

Notes on publication

The ift-Guidance Sheet „Advertising with ift test documents“ applies.

Identity-Check



www.ift-rosenheim.de/ift-geprueft
ID: 73F-7EE65

ift Rosenheim

20.09.2023

Thomas Krichbaumer

Thomas Krichbaumer
Deputy Head of Testing Department
Building Component Testing

F. Kugler

Florian Kugler, B.Eng.
Operating Testing Officer
Building Component Testing